Concrete Work

Scope:- These specifications are intended to cover all concrete work for the complete building, including foundation walls, foundations for columns and equipment, pits and other construction below ground; also all floors and roof construction. Window Sills, door sills, coping blocks, etc.

General:- The contractor, after the forms have been placed and before concrete is poured, is to give service system constructors ample time in which to place blocks, sleeves, inserts, pipes and other devices and attachments before pouring concrete, so that it will not be necessary for sub-contractors or others to cut any holes for pipes, conduits or other purposes.

Anchors and Miscellaneous Iron Work:- The contractor is to set and anchor all miscellaneous iron workerequired in concrete masonry.

Pipe and Other Openings:- Contractor is to provide pipe and other openings in foundations and other walls and floors, where specified, indicated or directed.

Protection of Conduit, Pipe, etc.:- The contractor to use extreme care not to move or dislocate any conduit, piping, hangers, or other systems installed in the floors.

Cement:- Portland Cement to be a well recognized brand to meet City specifications and requirements of the A.S.T.M.